

PROJECT NAME: SEWER CONDITION ASSESSMENT AND MASTER PLAN UPDATES

Database Manager [DEFAULT] - [Fields.ini]

Sort And Filter | WD Inspection List | WOH1 | Observations | Cross Section | Transfer Data

WD # Date Time

Footage Observation

Modifier CODE Str Grd OM Grd

Elapsed Time SF At To Dia % Int Gals

Clip

Image

Time	Footage	Observation	Modifier	Elapse	TIME	At	To
00>11:31:29	2.6	<START INSPECTION>		00:00:0			
00>11:33:00	20.1	"JOINT DISPLACED MEDIUM"		00:01:0			
00>11:33:20	23.3	"JOINT DISPLACED MEDIUM"		00:01:3			
00>11:33:42	29.4	"JOINT DISPLACED MEDIUM"		00:01:5			
00>11:34:12	31.9	"CRACK CIRCULAR AT 06 TO 05"		00:02:4		6	5
00>11:36:05	35.1	"KB TAR EXPOSED"		00:03:5			
00>11:36:56	43.2	"JOINT DISPLACED MEDIUM"		00:05:7			
00>11:38:33	49.6	"CRACK CIRCULAR AT 11 TO 05"		00:06:5		11	5
00>11:40:46	56.0	"MATERIAL CHANGE"		00:09:0			
00>11:40:52	56.0	"KB TO PVC"		00:09:7			
00>11:42:17	60.4	"CONNECTION AT 03 DIA 06 IN"		00:10:3		3	
00>11:42:53	61.2	"MATERIAL CHANGE"		00:11:0			
00>11:43:00	61.2	"KB TO VCP"		00:11:2			
00>11:43:55	68.1	"CONNECTION AT 09 DIA 06 IN"		00:12:7		9	
00>11:44:54	80.4	"JOINT DISPLACED MEDIUM"		00:13:7			
00>11:45:01	80.4	"MATERIAL CHANGE"		00:13:7			
00>11:46:00	85.5	"CONNECTION AT 09 DIA 06 IN"		00:14:2		9	
00>11:46:38	85.5	"MATERIAL CHANGE"		00:14:5			
00>11:46:49	85.5	"KB TO VCP"		00:15:5			
00>11:47:12	86.3	"JOINT DISPLACED MEDIUM"		00:15:2			

CIMS Video Player

18 (30) MH 65----- TO MH 64
Tue Dec 02 03
11:35:37
+0035.3

Playing 03:54 / 23:37

Playback Speed: 1x 1.5x 2x Size: 1x 2x Fit

WD: OBS: Video:

PROJECT NAME:	SEWER CONDITION ASSESSMENT & SEWER MASTER PLAN UPDATES				
Project Manager:	Director of Public Works				
Project Description:	This project will assess the condition of all sewer mains over six years and annually update the Master Plan to reflect emerging system rehabilitation priorities. This will be done in conjunction with the CCTV Project.				
Relationship to General Plan & Environmental Concerns:	This project is consistent with the implementing policies found in Section 6.2.c of the General Plan. The project is categorically exempt under Section 15301 Class 1(c) of the CEQA statutes.				
Total Project Planned Cost:	\$344,706				
Budgeting & Expenditure History:	<u>Fiscal Year</u>	<u>Original Budget</u>	<u>Adjusted Budget</u>	<u>Estimated/Actual Expenditure</u>	<u>Staff Request</u>
	FY 2009-10	50,000	50,000	44,706	N/A
	FY 2010-11	50,000	50,000	50,000	N/A
	FY 2011-12	N/A	N/A	N/A	50,000
	FY 2012-13	N/A	N/A	N/A	50,000
	FY 2013-14	N/A	N/A	N/A	50,000
	FY 2014-15	N/A	N/A	N/A	50,000
	FY 2015-16	N/A	N/A	<u>N/A</u>	50,000
				94,706	(Projection)
Sources of Financing:					
Sewer Fund				<u>94,706</u>	<u>250,000</u>
Total				94,706	250,000